

**Admin Parking Area Office Works\_Electrical\_Labour Work\_May-25**

Sr. No.	Item/Work Description	Unit	Qty	Rate in Rs.	Amount in Rs.
<b>Part C</b>	<b>Electrical Works (Only Labour)</b>				
1	6 Sqmm, Three Phase Circuit Wiring in PVC Conduit/Casing	Rmtr	30		
2	4 Sqmm, Single Phase Circuit Wiring in PVC Conduit/Casing	Rmtr	35		
3	2.5 Sqmm, Single Phase Circuit Wiring in PVC Conduit/Casing	Rmtr	90		
4	1.5 Sqmm, Single Phase Circuit Wiring in PVC Conduit/Casing	Rmtr	90		
5	1 Sqmm Light & Fan point wiring in PVC Conduit/Casing	Rmtr	90		
6	4/6/8 Module Plate with Switches/Socket & Internal Wiring	Each	40		
7	4/6/8 Module Backbox in Wall	Each	40		
8	DB with control MCBs, Circuit Connections etc. Complete	Each	1		
9	4FT, LED Light Fitting	Each	12		
10	15/22 Watt Surface LED Light Fitting	Each	15		
11	Ceiling Fan with Anchor Fastner	Each	8		
12	Exhaust Fan	Each	2		
13	20/25mm PVC Conduit pipe in Flooring Bedding.	Rmtr	60		
14	20/25mm PVC Conduit pipe in Wall with Zari Cutting and Finishing job	Rmtr	50		
15	20/25mm PVC Casing Capping Work	Rmtr	150		
<b>Total of Part C in Rs.</b>					