

Admin Parking Area Office Works_SITC Works_May-25					
Sr. No.	Item/Work Description	Unit	Qty	Rate in Rs.	Amount in Rs.
<b>Part A</b>	<b>Office Works</b>				
1	4" Brick masonry wall with both side single coat finish MALA plaster, gape filling job at existing column/ beam/ wall using chicken mess and coping work at two level with proper shuttering/farma works as per below details : >> Bottom coping works using two nos. 8mm horizontal bars and "C" shaped 2" x 3" x 2" bar with 8" spacing with grinding of existing IPS surface. >> Centre/Shield level coping work using 2 nos. 8mm horizontal bars and 3" vertical bars with 8" spacing. water curing, scaffolding etc. complete as per EIC.	Sqft	1050		
2	9" Brick masonry wall with inside single coat finish MALA plaster & out side double coat sand faced plaster, gape filling job at existing column/ beam/ wall using chicken mess and coping work at two level as below details : >> Bottom coping works using four nos. 8mm horizontal bars and 7" x 3" ring bar with 8" ring spacing with grinding of existing IPS surface. >> Centre/Shield level coping work using 2 nos. horizontal 8mm bars and 7" vertical bars with 8" spacing water curing, scaffolding etc. complete as per EIC.	Sqft	750		
3	Top RCC coping for 4" brick masonry with proper shuttering/farma works using two nos. 8mm horizontal bars and 3" ring bar with 8" ring spacing, both side finish MALA plaster, water curing, scaffolding etc. complete as per EIC.	Rft	45		
4	32mm Wooden flush door using ply sheet, both side 1mm lamination, vertical 5mm glass of 12" width x 5' height with liner frosted film, locking & fitting accessories i.e. hinges, handle, concealed lock, door closer, door stop etc. complete as per Admin GF Cabin door and EIC. Size 7' x 3'	Each	7		
5	Two step 19mm granite frame work fixing with tile adhesive & edge/side moulding/polish finish job etc. complete for 4" masonry cut-out of door/window/vent frame work as per EIC. Basic rate 120/Sqft	Sqft	100		
6	Two step 19mm granite frame work fixing with tile adhesive & edge/side moulding/polish finish job etc. complete for 9" masonry cut-out of door/window/vent frame work as per EIC. Basic rate 120/Sqft	Sqft	140		
7	600mm x 600mm single side polished kota type floor & skirting tiles with cutting, finishing and fixing in cut joint & joint filling using cement grout with approx. 50mm cement mortar bedding etc. complete as per approved sample of tiles and EIC.	Sqft	1400		
8	2 Track aluminium sliding window using 1.5/2 mm aluminium ivory powder coated frame, 5mm thick glass, sun control film, silicon sealant etc. complete as per EIC. Size 4' x 3'6" (3 Nos.), 5' x 3.6' (2 No.)	Sqft	90		
9	Two coats of Interior Distemper Paint after fill up crack with putti etc. complete (Asian Paints, 0387)	Sqft	3600		
10	Two coats of Exterior Paint after fill up crack with crack seal etc. complete (Asian Paints, 0387)	Sqft	1000		
11	Glassing work using Aluminium powder coated frame and both side 5mm thick glass with frosted non transparent film, silicon sealant etc. complete	Sqft	60		
12	32mm Wooden flush door using ply sheet, both side 1mm lamination, vertical 5mm glass of 12" width x 5' height with fitting accessories i.e. hinges, handle, door lock, door closer, door stop etc. complete Size 7' x 3'. 5mm thick Glass Partition work in wooden frame for 8'6"Ft x 5' Passage Entrance as per EIC.	Job	1		
<b>Total of Part A in Rs.</b>					