

Supply, Installation, Testing & Commissioning of Interior & MEPE Services at Lecture Theatre Building (G+2) at DAU Gandhinagar

Interior works for a Ground + 4 (G+2) Lecture Theatre Building						
Sr. No	Particulars	Location	Unit	Qty	Rate	Amount in Rs
	Acoustic Wall Panelling					
1	Wooden slats Type	Classroom	SQM	975.84		
	Providing and fixing acoustical wall paneling comprising a 50 mm GI stud framework securely fixed to the existing wall, including necessary GI channels, brackets, fasteners and accessories. The framework shall be infilled with 50 mm thick glass wool insulation of 48 kg/m³ density, wrapped in suitable acoustic-grade fibre cloth. The exposed face shall be finished with decorative wooden slats of approved material, each measuring 30 mm thick, with a uniform clear gap of 15 mm between adjacent slats, securely fixed to the GI framework using suitable screws or concealed fixing arrangements. The item shall include all materials, labour, cutting, fitting, alignment, levelling, jointing, edge finishing, wastage, scaffolding, tools, tackles and incidental works required to complete the installation in all respects, as per approved drawings, specifications, manufacturer's recommendations and the directions of the Engineer-in-Charge.					
2	PET Panel	Classroom	SQM	975.84		
	Providing and fixing acoustical wall paneling comprising 100 mm wide, 18 mm thick plywood battens securely fixed to the existing wall at suitable spacing, followed by fixing 9 mm thick PET acoustic panels in approved shade over the battens using suitable adhesive and/or mechanical fasteners, including cutting, fitting, jointing, alignment, edge finishing, necessary hardware, labour, materials and all incidental works to complete the installation in all respects as per approved drawings and the directions of the Engineer-in-Charge					
3	Plain Panelling - 12mm Laminated Ply Panelling	Classroom	SQM	627.33		
	Providing and fixing 12 mm thick plywood paneling on walls, finished with approved shade and texture of decorative laminate, using suitable adhesive and/or screws over an adequately secured supporting framework or battens as required. The item shall include cutting, fitting, jointing, edge finishing with matching edge bands, necessary screws, adhesives, fasteners, labour, wastage and all incidental works to complete the paneling in all respects as per approved drawings and the directions of the Engineer-in-Charge					
Basic Amaount in Rs.						
GST						
Total Amount in Rs.						