

**Supply, Installation, Testing & Commissioning of Interior & MEPE Services at Lecture Theatre Building
(G+2) at DAU Gandhinagar**

INTERIOR WORKS BS-MS Building G+2						
Sr. No	Particulars	Location	Unit	Qty	Rate	Amount in Rs
	False Ceiling					
1	Modular Ceiling	Classroom	SQM	1,672.86		
	Providing and fixing suspended acoustic false ceiling using 600 × 600 × 15 mm thick mineral fibre microlook edge ceiling tiles, having a Noise Reduction Coefficient (NRC) of 0.50, Make: Amazone Sand or approved equivalent, laid on a 15 mm wide pre-coated GI exposed grid system, Make: Amazone / Techno or approved equivalent. The work shall include main runners, cross tees, wall angles, suspension rods, hangers, soffit cleats, fasteners, levelling, cutting, fitting, necessary openings for lights and services, wastage, labour, scaffolding and all accessories required to complete the installation in all respects as per approved drawings, manufacturer's recommendations and the directions of the Engineer-in-Charge.					
2	Painting - Providing and applying premium-quality acrylic emulsion paint of approved make, shade and colour on interior wall and ceiling surfaces, including preparation of the surface by removing loose particles, dust and other foreign matter, applying suitable wall primer, filling minor cracks and surface imperfections with approved wall putty wherever required, sanding smooth, and applying two or more coats of premium acrylic emulsion paint to obtain a uniform, smooth and even finish. The work shall include all materials, labour, scaffolding, tools, tackles and incidental works complete as per the manufacturer's recommendations and the directions of the Engineer-in-Charge.	Classroom	SQM	4,042.74		
Basic Amaount in Rs.						
GST						
Total Amount in Rs.						