

**Supply, Installation, Testing & Commissioning of Furniture in Lecture Theatre Building (G+2) at
DAU Gandhinagar**

Sr. No	Particulars	Unit	Qty	Rate	Amount
	Acoustic Wall Panelling				
1.1	Wooden slats Type	Sft	10,500.00		-
	P/f Acoustical paneling consisting 50mm GI Studs framing fixed on wall, followed by 50mm Rockwool wrapped in Fiber cloth as infilling material. Finally, Wooden Slats of will be fixed on GI Studs				
1.2	PET Panel	Sft	10,500.00		-
	P/f Acoustical paneling consisting 100mm wide 18mm thick Ply battens fixed as a base on wall. 9mm PET Panel in approved shade will be fixed on the Ply battens.				
2	Plain Panelling - 12mm Laminated Ply Panelling	Sft	6,750.00		-
	P/f Laminated Ply paneling consisting 12mm thick Ply fixed on wall.				
3	Ceiling				
3.1	Gypsum Ceiling	Sft	21,600.00		-
	12.5mm Plain Gypsumboard fixed to the Concealed GI Framing suspended from slab. Finally, all the joints will be finished with jointing compound & fiber tape.				
3.2	Modular Ceiling	Sft	18,000.00		-
	600x600x15mm. Thick Mineral Fiber Microlook Edge Tiles having 0.50 NRC (Make : Amazone Sand) Laid in 15mm Plain GI Precoated Grid (Make : Amazone / Techno) .				
4	Wooden Doors				
4.1	Double Door (2000x2100) - on open door closer	Nos	12.00		-
	100 mm Hollow Wooden Laminated Flush door with Rockwool as infill material and Gaskets on Edge. Hardware consists of 100Kg. Open Door closer, 5" X 2" SS Hinges, 400mm. H /D Shaped Handle & Lock body with OKOT Type Cylinder.				
4.2	Single Door (900-1050x2100) - on open door closer	Nos	43.00		-
	40mm Wooden Laminated Flush door with Open Door closer, 5" X 1.5" SS Hinges, 400mm. H /D Shaped Handle & Lock body with OKOT Type 70mm Cylinder.				
5	Wooden Door Frames - Laminated Ply				
5.1	Double Door Frame (2000x2100) 150mm. x 100mm. Door frame made out of 18mm Laminated Ply in step type design	Nos	12.00		-
5.2	Single Door Frame (900-1050x2100) 100mm. x 50mm. Door frame made out of 18mm Laminated Ply.	Nos	19.00		-
6	Desk as shown in 3D - 16 Gauge MS Powder coated Structure with Prelaminated Board Top.				
6.1	6 Pax	Nos	288.00		-
6.2	7 Pax	Nos	168.00		-
7	Podium Table - Laminated Ply Top with Metal Structure	Nos	6.00		-
8	Podium Chair	Nos	6.00		-

Sr. No	Particulars	Unit	Qty	Rate	Amount
9	Painting - Acrylic Premium Emulsion	Sft	43,500.00		-
10	Providing and installing the staff table for cabins table-top along with height as per architectural detail drawing out of post-formed laminated of approved design with smooth edges and having necessary structural frame made out of pre-laminated ply fins of the same design as per architect Drawing, brush-finished. HOF/BP-ergo/Haworth or equivalent.The rate includes the cost of providing metal keyboard pull-out tray, CPU Trolley, wire manager etc. with all necessary hardware fittings .All hardwares like locks, handles, pivots, hinges used are to be of ebco, ozone, dorma or equivalent. Complete.As per design by Architect. complete as per design/drawing/location and consultant's instructions [6'-0"x2'-6"x2'-6"]	Nos	8.00		-
11	Providing and installing the staff table for (Cubical table) table-top along with height as per architectural detail drawing out of post-formed laminated of approved design with smooth edges and having necessary structural frame made out of pre-laminated ply fins of the same design as per architect Drawing, brush-finished. HOF/BP-ergo/Haworth or equivalent.The rate includes the cost of providing metal keyboard pull-out tray, Drawer with lock, CPU Trolley, wire manager etc. with all necessary hardware fittings .All hardwares like locks, handles, pivots, hinges used are to be of ebco, ozone, dorma or equivalent. Complete.As per design by Architect. complete as per design/drawing/location and consultant's instructions [4'-6"x2'0"x2'-6"]	Nos	20.00		-
12	Providing Medium-back staff chairs: 660 mm x 640mm x 950mm (LXBXH) with thick padded seat and back out of PU moulded foam in the approved fabric upholstery, PP (polypropylene) armrest with front curvature, synchro mechanism with upright locking position. adjustable height by hydraulic gas lift mechanism, 5 pronged moulded polypropylene (PP) base with 100 % nylon castors. HOF/featherlite or equivalent or As per approved.	Nos	28.00		-
13	Providing and fixing 75 mm thk wooden partition with Glass vision panel in line, level and plumb made out of 50 mm X 35 mm thk aluminium framework @ 600 mm c/c with 6 mm thk commercial ply fixed on both the sides of the frame work Laminate Finish etc. all complete as per architects instructions. , 75mm x 25mm cover moulding in TW as Trim on top and side	Sft	300.00		-

Sr. No	Particulars	Unit	Qty	Rate	Amount
14	Providing and fixing storage cabinets -As per site suitability height minimum - 400mm to 600 mm deep: using 18mm thick MR-grade commercial ply and shelves of 12mm ply of Greenply, Archidply or equivalent make. A drawers of 150mm height on channels of ozone/ebco make is made using 12mm thick commercial MR-grade plywood. All exposed ply surfaces to be covered with 6mm thick seasoned saal wood melamine polished beading putties using nails and adhesives. The plywood box is enclosed using 18mm+6mm thick ply shutter on pivots/hinges of full height. All hardwares like hinges, pivots, magnets, handles, locks, fasteners to be of ebco, ozone, dorma or equivalent make. complete at all levels and all heights.As per design by Architect.	Sft	140.00		-
15	Providing and Fixing Roller Blind as approved shade & fabric.the blind shall be made out of extruded aluminium alloy of 48mm outer dia. With a minimum wall thickness of 1.1mm duly anodised for long life. The tube shall be designed with support ribs to keep it straight and shall have a pocket for holding the fabric in position. the operating mechanisium shall consist of a gear with spring booster. the mechanisium shall be designed using high strength fibred glass reinforced polyster assembly and high carbon steel spring to transmit motion from driving to driven members. the min. spring torque shall be 16kg per cm to ensure ultra smooth operation of blinds of up to 3m width and 4m drop. The rate also includes for all necessary items required to complete the job as per design/drawing and client/consultant's instructions.	Sft	50.00		-
Amount					
GST 18%					
Total Amount					-