

**DAU\_Mess Washroom Renovation\_Electrical Works\_SITC Works\_Sept-25**

Sr. No.	Item/Work Description	Unit	Qty	Rate in Rs.	Amount in Rs.
1	Single Phase Three Wire, 2.5 Sqmm (PNE) Copper Flexible Wire Circuit Wiring with Accessories & Connections etc. Complete as per EIC.	Rmtr	30		
2	Single Light Control Point using 1 Sqmm Copper Flexible Ckt Wiring, Switches, Switch Plate, Back box, Accessories & Connections etc. Complete as per EIC.	Each	8		
3	Loop Light Control Point using 1 Sqmm Copper Flexible Ckt Wiring, Switches, Switch Plate, Back box, Accessories & Connections etc. Complete as per EIC.	Each	8		
4	Power Point using Separate 6Amp Switch & Socket, Back box, Single Phase Three Wire, 2.5 Sqmm (PN) x 1.5 Sqmm (EH), Copper Copper Flexible Wire Circuit Wiring with Accessories & Connections etc. Complete as per EIC. (5Mtr)	Each	6		
5	On Board 6Amp Power Point with Switches, Sockets, Switch Plate, Back box with Accessories & 1.5 Sqmm Wire Connections etc. Complete. As per EIC.	Each	2		
6	22 Watt Round White Deep Down Panel LED Light with 2 Years Warranty, Fix with necessary connections etc. complete. Basic Rate 800/-	Each	4		
7	18 Watt Round White Deep Down Panel LED Light with 2 Years Warranty. Fix with necessary Connections etc. complete. Basic Rate 600/-	Each	12		
8	300mm PVC, Crompton Make Brisk Air Exhaust Fan and Fix in aluminium frame with necessary clamps/support, connection etc. complete	Each	4		
9	20/25mm PVC Conduit Pipe Laying with Zari work in brick masonry wall using electrical cutter/breaker. Finish zari work using chicken mess, single coat finish plaster with line & level etc. complete as per EIC.	Rft	100		
10	2/4/6/8/12 Module MS back box fitting work in brick masonry wall using electrical cutter/breaker. Finish gape with single coat finish plaster with line & level etc. complete as per EIC.	Each	8		
	<b>Total in Rs.</b>				

**All kinds of Circuit/Point wiring will be in PVC Conduite/Cassing Capping/Flexible Pipe etc. as per EIC**

**PVC Conduite/Cassing Capping/Flexible Pipe etc. will be laid on Wall/ False Ceiling/ in Partition etc. as per EIC**